



Pre-Terminated Heater with In-Line Thermostat

Applications

Thermotex Pre-Term is a Pre-Terminated Heater with an In-Line Ambient Sensing Thermostat, intended for a single run installation on outside drains to protect against frost.

Available Lengths

- 1m
- 2m
- 3m
- 5m
- 6m
- 7m
- 9m
- 10m
- 12m

Technical Data

Location:	Outdoor Use
Traced Surface:	Metal Pipes or Plastic Rain Water Systems
Solar Performance:	UV Stabilised
Operating Temperature:	-20°C to +30°C
Minimum Installation Temperature:	-10°C
Thermostat Switch On Temperature:	ON at 3°C, OFF at 8°C (±3°C)
Switch Type:	Mechanical
Voltage:	230V AC
Max Load:	5A

Other

Approvals: CE Marked

Thermotex recommends the use of a 30mA residual current device for maximum safety

